



# SR 2006, Section 476 MacDade Boulevard Interchange

ITE Mid-Colonial District – 2026 Annual Meeting  
April 16, 2026



# SR 2006, MacDade Blvd - Project Team

## Owner & Design Team


- **Owner** – PennDOT District 6-0
- **PennDOT Consultant PM** - *Kristin Caparra, AECOM*
- **HDR** – Lead Designer (*Bill Laird – Design PM*)
- **Drive Engineering**
- **Navarro & Wright**
- **A.D. Marble**

## Construction Team

- **Allan Myers** – Contractor
- **Urban Engineers** – Construction Management
- **CMC Engineering** – Construction Inspection

# Project Location


- SR 2006, MacDade Boulevard Interchange is Exit 1 on I-476.
- Just north of I-95
- Interchange carries over 30,000 vehicles per day.
- Vital connection from I-95/I-476 to local communities.
- MacDade Blvd serves as Gateway to Ridley Township



# Project Background & Description

MacDade Boulevard Interchange originally constructed in 1992 as part of the I-476 Mid-County Expressway (Blue Route Project.)

- Increased traffic volumes and development along I-476 and MacDade Boulevard overwhelmed capacity
- Interim fixes to improve safety were no longer effective



# Purpose and Need

Project was warranted due to the following considerations:

- Address operational challenges and safety concerns related to existing I-476 NB ramp to MacDade Blvd East (Ramp 7).
- Deficient Sight Distance on Ramp 7 due to existing Pedestrian Structure that extended over ramp.
- Congestion improvement along I-476 during peak hours due to insufficient merging distances at the ramps.
- Improve safety and operation of the Bullens Lane and MacDade Blvd intersection.



# Project Description & Complexity


Complex project contained an expansive scope of work.

- MacDade Blvd Interchange ramp reconfiguration.
- Complex structure widening/design.
- Evaluation and addressing I-476 NB traffic backups at Interchange ramps.
- Complex maintenance and protection of traffic.
- Traffic Signals/ITS/DMS facilities.
- Extensive Utility/SUE involvement.
- Comprehensive NPDES/Permitting Coordination.

# MacDade Blvd/I-476 Interchange

## Operational/Safety challenges

- Examination of inefficiencies and safety issues due to cut-through traffic.
- Improvements to ramp termini.
- Pedestrian safety/movements along MacDade Blvd.
- I-476 Operational Improvements.





# Ramp M-3 Reconfiguration

Ramp widening needed to accommodate additional Ramp 7 traffic once removed.


## Existing Condition

- One 15' travel lane

## Proposed Condition

- Two 12' min travel lanes

Shoulders reconstructed to handle traffic during staging.



# I-476 Interim Operational Improvements


- HDR/PennDOT evaluated potential to improve traffic operations, travel time and safety along I-476 NB for traffic coming from I-95.
- VISSIM modeling conducted by the team showed reduced congestion and improved travel times along I-476 with the interim traffic improvements taken on by the project.
- To optimize effectiveness, improvements were needed at both heavy ramp merge areas of I-95 into I-476 and further north on I-476 at US 1.
- The project constructed interim improvements to alleviate peak hour congestion on I-476 prior to longer term improvements for flex lanes.

# I-476 at MacDade

Existing northbound outside shoulders were converted to extend auxiliary lanes.

This allowed for up to four 11' lanes on I-476 through the MacDade Blvd. interchange.

Included a 2' shift in traffic towards the median due to bridge barriers and sight distance issues.




SR 0476 NORTHBOUND  
AT MACDADE BLVD INTERCHANGE

# I-476 at US 1

Converted shoulder to auxiliary lane just north of the I-476 & US 1 interchange on-ramp at Media Bypass (US 1).

These improvements added enough increased capacity to allow for a decrease of peak travel times along the corridor of ~ 17 minutes.



# MacDade Blvd/Bullens Lane Intersection

Lack of a separate EB left turn lane presented operational and safety issues.

- Left turning vehicles needed to occupy the inner through lane leading to rear-end crashes.

Existing ADA ramps did not meet requirements.

No signal interconnection with corridor signals.



# MacDade Blvd Signals

New traffic signals installed at the Bullens Lane and I-476 Northbound Ramp intersections.




# MacDade Blvd Signals

- Improvements to the existing MacDade Blvd traffic signals at the intersections at Fairview Road and the I-476 Southbound Ramps included the installation of upgraded traffic signal equipment in the controller cabinets to accept the fiber optic cable interconnection and well as emergency vehicle pre-emption.
- Improved traffic signal timings to optimize the progression of traffic along MacDade Blvd.



# MacDade Blvd Pedestrian Improvements

- Pedestrian design focused on connectivity – long term & during construction.
- Residential community on SW quadrant of MacDade Blvd and Bullens Lane utilized existing, unsafe pedestrian routes to access commercial area of MacDade Blvd.
- ADA Ramp improvements.



# ITS/DMS Facilities

Project added CCTV and DMS facilities along the corridor.

Substantial coordination with PennDOT, Blair Park and external contractors.




# Utility Coordination

Substantial utility coordination and SUE investigations.

- 10 Utility Companies
- 70+ Potential Conflicts
- 32 SUE test holes

Commonwealth-wide utility coordination pilot project whose conflict avoidance activities served as a precursor to and development of URMS.



MacDade Utility Conflict Test Hole Locations							2/13/2019
Alignment	Station	Offset	Approximate Test Hole Depth	Utility	Location relative to traffic	Applicable PATA Figures	
Test Holes Highlighted Yellow were previously drilled in September 2018							
MacDade Blvd	1 24+54	33' RT	10	Underground Petroleum line	Outside curb of EB MacDade	PATA 124 (Work Space in the Left or Right lane of Two-Lane approach) PATA 405 (Lane Closure Near a Freeway or Expressway Entrance Ramp)	
MacDade Blvd	2 27+72	33' RT	10	Underground Petroleum line	Outside curb of EB MacDade	PATA 124 (Work Space in the Left or Right lane of Two-Lane approach) PATA 405 (Lane Closure Near a Freeway or Expressway Entrance Ramp)	
MacDade Blvd	3 30+00.00	8.98' LT		Underground Electric	Median		
MacDade Blvd	4 28+40	33' RT	10	Underground Petroleum line	Outside curb of EB MacDade	PATA 124 (Work Space in the Left or Right lane of Two-Lane approach) PATA 405 (Lane Closure Near a Freeway or Expressway Entrance Ramp)	
MacDade Blvd	5 30+99.77	40.19' RT		Underground Electric	4' outside of Ramp 7 (to be obliterated).		
MacDade Blvd	6 31+13.15	5.09' LT		Underground Electric	Median		
MacDade Blvd	7 31+50.64	33.00' RT		Underground Gas line	3' inside existing curb line of outside lane		
MacDade Blvd	8 29+00	9' LT	9	Underground Electric	Inside median of WB MacDade	PATA 124 (Work Space in the Left or Right lane of Two-Lane approach)	
MacDade Blvd	9 33+64.38	8.87' LT		Underground Gas line	Median		
Ramp 7 Existing	10 43+42	29' RT	6	Underground Electric	20' right of outside edge of Ramp 7	N/A	
MacDade Blvd	11 34+54.48	37.87' RT		Underground Electric	Behind existing guiderail and fence along MacDade		
Ramp M-3	12 * 41+03	11' RT	2	Underground Fiberoptic	Outside edge of guiderail Ramp M-3 at begin bridge over MacDade	PATA 406 (Work Space on a Ramp)	
MacDade Blvd	13 41+32.50 (AHEAD)	33.00' RT		Underground Electric	1' inside existing curb line of outside lane		
MacDade Blvd	14 31+19	23' LT	4	Underground Water line	Within right lane WB MacDade	PATA 124 (Work Space in the Left or Right lane of Two-Lane approach)	
MacDade Blvd	15 41+99.01 (AHEAD)	37.60' RT		Underground electric and gas	Behind existing guiderail along shopping center.		
MacDade Blvd	16 31+50	9' LT	8	Underground Gas line	Inside median of WB MacDade	PATA 124 (Work Space in the Left or Right lane of Two-Lane approach)	

# Stormwater/Drainage/NPDES Permitting

Drainage pipes/inlets and swales added along MacDade Blvd.



NPDES Permit – to incorporate PADEP changes in regulations, permits were required to be updated multiple times during design, the last during the COVID shutdown.

# Traffic Control

## MacDade Blvd Interchange

Access maintained at all times.

9 total stages – mix of short and long-term operations.

Tight work zones required to keep traffic moving efficiently

No interruptions of pedestrian usage

### Stage 1

- MacDade Blvd median removal

### Stage 2

- Ramp M-3 pavement widening
- Partial width construction of Ramp M-3 structure

### Stage 3 & 4

- Staged pavement/barrier construction of the MacDade Blvd/Ramp Intersection

### Stage 5

- Completion of Ramp M-3 pavement/structure.
- New signal construction at MacDade Blvd/Ramp Intersection

### Stage 6 & 7

- Pedestrian Bridge/Sidewalk construction
- Removal of Ramp 7 & drainage work

### Stage 8 & 9

- Reconstruction of MacDade median and final paving.

# Traffic Control

## I-476 NB Construction

Work Zone Analysis memo and Work Zone Impact Delay Analysis completed

Lane closures allowed for short-term operations on weekends and overnights

Lane closures must avoid Philadelphia events:

**May, 2023 – Taylor Swift Eras Tour**


### Stage 1

- I-476 NB Inner/Outer shoulder reconstruction
- Minor drainage work on outside shoulder

### Stage 2

- I-476 Mill & overlay of entire roadway
- Installation of new pavement markings and roadside signs
- Installation of sign overlay panels on overhead signs
- Ramp 6 mill & overlay

# Ramp M-3 Bridge – Proposed Typical Section



**TYPICAL SECTION**  
(LOOKING AHEAD STATION)

# Ramp M-3 Bridge Widening

Two 12' Wide Lanes

Curved Girder Widening,  
One Girder Line Added

Cross-Frames at Floorbeam  
Locations

3D Superstructure Analysis  
performed by BSDI

Stand-alone Pier Columns,  
Widened Abutments



Jul 25, 2023 at 10:20:17 AM  
I-476 N  
Woodlyn PA 19094  
United States

*Photo: Urban Engineers*

© HDR 2024, all rights reserved.

# Existing Pedestrian Structure

Network of two-girder bridge spans and concrete ramps

- Crum Creek Crossing
- Ramp 7 Crossing
- Residential Neighborhood Connection

Total **540'** of steel bridge length, **8 spans**, and **300'** of concrete ramp structures



# Existing Pedestrian Structure




# Replacement Pedestrian Structure

- Removed 8 spans and 2 concrete ramp structures
- Single span bridge over Crum Creek and at-grade sidewalk




# Replacement Pedestrian Structure



# Notable Construction Challenges

## Traffic Control During I-476 Operations

- Managing I-95 NB/SB ramps to I-476 during resurfacing
- Needed additional traffic control, crash trucks and State Police Support



## Intricate Construction Staging

- 9 Stages created smaller work areas, resource fluctuations and extended duration of work
- Minimized durations by working in multiple stages concurrently

# Notable Construction Challenges

## Diversity of Scope of Work

- Multiple crews needed – Structures, Excavation, Paving, Pipe, Electrical, Signals & DMS to name a few
- Coordination was the key to success

## Underground Utilities

- Detailed coordination with 3 major pipelines
- Modifications needed in drainage to avoid undetected/unknown PECO High Voltage Underground Electric line



# Project Construction Schedule

	<u>PreBid</u>	<u>Actual</u>
Project Let	March-22	March-22
Notice to Proceed	May-22	May-22
Physical Construction Begins	Jun-22	Sept-22
MacDade Blvd/Ramp Intersection Open	May-25	Dec-23
Pedestrian Bridge Complete	Aug-25	May-24
Ramp 7 Removal Complete	Apr-25	Sept-25
Project Final Walk Through	Aug-26	Dec-24

**615 Days Early**

# Project Construction Schedule

## How did they save so much time??

- Pre-Bid Schedule was sequential by stages with Winter shutdowns
- Allan Myers was able to adjust resources
  - Concurrent work with Stages 2, 3 & 4
  - Concurrent work with Stages 5 & 6
  - Concurrent work with Stages 8 & 9
- Work proceeded through Winter with no shutdowns

## Construction Costs

Design Estimate - \$14.5 M

Bid Estimate - \$16.2 M

Final Cost - \$18.1 M

## Top 3 Impacts to project cost:

- Change to SMA paving on SR-476 with the added void reducing asphalt membrane (VRAM) - **\$800K**
- Final mill/overlay added to MacDade Blvd. - **\$550K**
- MacDade Crossing Shopping Center Intersection added via HOP to contract - **\$400K**

# Ramp M-3 Intersection Construction



*Photo: Allan Myers*

# Ramp M-3 Intersection Construction



*Photo: Allan Myers*

Ramp M-3 Bridge  
Widening  
Construction

Deck Cut

May 1, 2023 at 1:42:22 PM  
Woodlyn PA 19094  
United States



*Photo: Allan Myers*

Ramp M-3 Bridge  
Widening  
Construction

Mar 9, 2023 at 1:04:41 PM  
Woodlyn PA 19094  
United States



*Photo: Urban Engineers*

Ramp M-3 Bridge  
Curved Girder  
Erection



*Photo: Allan Myers*

Ramp M-3 Bridge  
Widening  
Construction



*Photo: Allan Myers*

Ramp M-3 Bridge  
Widening  
Deck  
Construction



*Photo: Allan Myers*

Replacement  
Pedestrian Structure  
Erected



*Photo: Allan Myers*

Replacement  
Pedestrian Structure  
Deck Construction



*Photo: Allan Myers*

Ramp Intersection at  
MacDade Blvd



Ramp Intersection at  
MacDade Blvd



# Widened Ramp M-3 Structure



Replacement  
Pedestrian Structure



*Photo: Urban Engineers*

Replacement  
Pedestrian Structure

Ramp 7 Removed



*Photo: Urban Engineers*

***Thank you!***

**Questions?**